FOR MYSORE STATE

4-1-52.

Public (C. P. Audit) (1953) Department.

SERIES.

G.O. NO. MS. 786

Dated 23-3-1953.

Passed
27/4/53
Superintendent

G.o at p 7 4

[Despatch Abstract.]

Community Projects - South Kanara Dt. - Drinking water Supply - Construction of a well in R.S. No. 8/2 of Karnad village - Estimate - Sanctioned.

4702

Ref.C.No.415/52-C. Office of the Project Executive Officer, South Kanara, Mangalore, Dt. 6-3-53.

From

Sri G.Simhadri, B.A.,
Project Executive Officer,
Mangalore.

To

The Director of Community Projects
and Ex-Officio Secretary to Govt.,
Fort St.George, Madras 9.

....

Sir,

COMMUNITY PROJECTS - South Kanara - Drinking water supply - Sinking of a well in Karnad village.

****

The proposal is to sink a new public well at the site marked 'S' in the eye-sketch in S.No. 8/2 of Karnad village. The site is near the public Maidan called 'Gandhi Maidan' in Karnad village. There are about 50 houses within a radius of one furlong of the proposed site. Scarcity of water especially in the hot months is greatly felt in this locality. The proposed well would benefit these 50 families, besides pedestrians and cartmen.

2) The site has been approved by the Health Inspector. The pits referred to by him, can be filled up with the excavated earth.

3) The proposal to sink a well at this site has been approved by the Project Advisory Committee and is included in the work programme for 1952-53. The people are prepared to contribute 25% of the cost. The work is estimated to cost Rs. 4,210/- The peoples' contribution forthcoming is Rs. 1,052-8-0. The balance of Rs. 3,157-8-0 has to be met from the Community Project funds. The estimate may be sanctioned for Rs. 3,157-8-0 As regards the cost, I enclose herewith the estimated cost of construction of wells under the Rural Water Supply scheme. The list shows that the average cost of construction is in the neighbourhood of Rs. 4,000/-

Detailed estimates in duplicate are enclosed.

PROJECT EXECUTIVE OFFICER.

T/6.3.

Sl.No.	Name of the Scheme.	Department to which the scheme relates.	Total approximate cost of the scheme.

Block No. I: (Mangalore Taluk) — Mangalore, Gurpur, Surathkal and Moolky (Sankar)

Schemes in the five year plan:-

Rural Water Supply comprehensive Scheme. 1948-1953.

Mangalore Firka.

1.	Kotekar, S.No.38/1 A	Rs. 3,980
2.	Boloor, S.No. 15/a*1A	Rs. 4,100

Gurpur firka.

1.	Thiruvail 9-1E	Rs. 4,495
2.	Tenkayedapadavu 28-1	Rs. 3,650

Surathkal Firka.

1.	Kanoor	Rs. 3,500

Moolky Firka.

1.	Hejamady, S.No.189/A/A2	Rs. 3,870
2.	Talepady. 300-5	Rs. 4,000
3.	Mannabettu 46-12	Rs. 3,600
4.	Koondamule 32-3A	Rs. 4,090
5.	Balkunje, S.No. 59-1	Rs. 4,000
6.	Mulladka.	
7.	Mundkur. 287-1	Rs. 4,500

Block No. II. Mangalore Taluk (Panemangalore and Buntwal firkas)
Karkal Taluk (Moodabidri and Venoor Firkas)

Panemangalore Firka.

1.	Thumbe 94-2	Rs. 4,500

Buntwal Firka.

1.	Rayee 73-A	Rs. 3,770
2.	Pilimogar 82-8	Rs. 4,100

Moodabidri Firka

1.	Thodar 150-2B	Rs. 4,100

Venoor Firka.

1.	Naravi 58-3	Rs. 4,490
2.	Karimanel 4-1	Rs. 4,100
3.	Nittade 26-1B	Rs. 4,000
4.	Tenkakarandoor 87-1	Rs. 3,780

Block No. III Karkal Taluk (Karkal and Ajekar Firkas)
Coondapur Taluk (Coondapur, Wandse & Baindur Firkas)

Karkal Firka.

1.	Nitte 259-2A1B	Rs. 2,200
2.	Mizar ~~266-3A~~ 372-3	Rs. 4,450
3.	Karkal 266-3A	Rs. 4,230
4.	Kukundoor. 217-1A1	Rs. 2,600
5.	Nire. 108-1	Rs. 3,200
6.	Belmon. 48-a*1A	Rs. 4,490
7.	Nadalike. 34-a*1A	
8.	Belmon (earth filling of the abandoned site)	Rs. 85

1.	2.	3.	4.
Ajekar Firka.			
1.	Yerlapady. 386-1		Rs. 4,400
2.	Mudradi. 77-2A1		Rs. 5,000
3.	Ajekar. S.No.135/A1		Rs. 1,950
4.	Ajekar another S.No. 135/A1		Rs. 2,300
5.	Hebri. 61-1B		Rs. 4,490
Coondapur Firka			
1.	Belve. 65-a 1		Rs. 3,700
Wandse and Baindur Firkas.			
- nil -			

/ True copy /

~~PROJECT EXECUTIVE OFFICER.~~

Pub (CP. Audit) Dept.

[C. No 4702/53]

G.O. Ms. 786 dt. 23-3-1953.

Abstract- Community Projects- South Kanara District- Drinking water Supply- Constructing a well in R.S. No 8/2 of Karnad village- Estimate-Sanctioned.

Read- From the P.E.O Mangalore- ref C No. 415/52-C dt. 6-3-53

C.F.

Orders:-

Sanction is accorded to an expenditure not exceeding Rs 2748/. (Rupees Two thousand Seven hundred and forty eight only). out of an estimated cost of Rs 3800 for Constructing a new well for drinking water in R.S. No. 8/2 of Karnad village. The balance of Rs 1052/. required to complete the work should be met from Contributions from the beneficiaries

2. The expenditure should be debited to "63 B Community Development Projects II. Community Projects- c. Health and rural Sanitation 2. Drinking water Supply".

The P.E.O should get the work executed according to the approved plan and estimate herewith enclosed and should submit a Completion report to Govt in due course.

To The P.E.O. Mangalore (with enclosures)

To The A.G. (Madras)

To Pub (CP. Accts.) Dept

.. to Pub (CP. Tech) Dept

.. to Pub (CP Audit) ..

S.F.

C.B. 10 weeks.

Entered in C.B.

S.F.:

Note:- Please see p. 2 of C.F.

The estimate has been scrutinized and is in order. Slight Corrections in rates due to adoption of the lowest provisions of the current Schedule of rates for conveyance of materials, have resulted in an estimated cost of Rs 3800 as against Rs 4210 estimated by the P.E.O.

The Site chosen has been approved and certified by the Sanitary inspector.

As mentioned in the report accompanying the estimate, the depth to be dug and the nature of Subsoil, have been estimated by reference to private wells nearby. The estimated water level is also thus arrived at.

The proposal is to Construct a well of inner diameter 8 feet and

para 2 of C.F. p. 1

a depth of 40 feet. As Soft clay is expected between depths 30' and 40' Steining of laterite in cement mortar is proposed for the entire depth, resting on a Kerb of Reinforced Cement Concrete. This Steining will be plastered with Cement mortar above low water level. & the normal provisions for platform, parapet drains and pulley arrangements are also made.

The PEO has reported that the people's Contribution is Rs 1052/8 being a fourth of the Rs 4210, the cost as estimated by the P.E.O. This amount or (Rs 1052/-) may be taken even more, as the people's Contribution. The estimate may therefore be ~~Sanctioned~~ approved and Sanction accorded for an expenditure of Rs (3800 - 1052) or Rs 2748/-

The draft order ~~above~~ except may please be approved. The estimate may also be signed in token of Sanction

Kept below

19.3.53

20/3/53

21/3/53

21/3

[Issued as G.O. MS. No. 786 Public (C.P. Audit) Dept. d/23 3/53]

Entries in Statement

21.3.53